



Michigan Department of Transportation

Construction Project Information Sheet

Date: April 23, 2020

Office: MDOT Cadillac Transportation Service Center

Status: Revised, 04/06/2020. **Project is scheduled to resume on 05/04/2020**

Roadway: M-91

CS & JN: Control Section 59032 & Job Number 125967

Region/County: Grand/Montcalm County

Closest City: Greenville

Exact Location: M-91 from just south of Peck Road northerly to just north of Colby Road

Project Length: 3.82 Miles

Nature of Work: Hot mix asphalt cold milling and resurfacing, NB offset right turn lane at Peck Road, extend the center left turn lane north of Peck, construct center left turn lane north & south of Colby Road, joint repairs, safety & drainage improvements, and pavement markings.

Start Date: April 13, 2020; with tree removals scheduled for the first week of March.

Est. Completion: July 2020

Traffic Impacts: Traffic shall be maintained by detours, 1 alternating lane open under flag (traffic regulator) control, or shoulder closures. No Sunday work.

Total Cost: \$4,129,000.00

Customer Benefit: The original concrete road was constructed in 1925. It has since been widened, resurfaced and had joint repairs. This project will improve traffic flow, safety, ride quality, and drainage.

Project Staff / Contact Information

Project Engineer: Craig Taylor, MDOT Cadillac TSC (231) 884-8658

Construction Engineer: Kevin McReynolds, MDOT Cadillac TSC (231) 775-3486

MDOT Media Contact: John Richard, MDOT Grand Region (616) 451-4063

Contractor Contact: Nick Byrne, Michigan Paving & Materials Co (616) 481-9895

In the event of an emergency contact the Contractor's 24 hour Emergency Contact.

If the Contractor is not available, contact the Project Engineer.